

	Document Title:	Doc No:	FRM B1-02	
	Structural Performance Certification Authorization Report	Rev No: 7	Page: 1	Of: 1
Required By: PRO B1-03				

CAR & Product ID Number: 757 - 142.0
Issue Date: 4/16/2021
Revision Date: 4/16/2021
Expiration Date: 4/16/2025
Company Code: 757

This Certification Authorization Report (CAR) is issued by Keystone Certifications, Inc. (KCI) after full validation review, and is based on a standardized evaluation of the product conducted by an independent accredited laboratory in accordance with the specified referenced standard. Actual fenestration product performance may vary based on many factors, including installation, condition of the wall/roof substrate and the age of the product and installation components.



This report indicates the product is eligible for the application of Keystone Certification Program certification labels. Licensee stipulates in affixing certification labels to products, that those products are representative of the specimen evaluated and documented for certification authorization. Only products bearing such a certification label shall be considered certified. The information in this report can be verified at www.keystonecerts.com.

Licensee Information:	Product Information:
Pocahontas Aluminum Company, Inc. PO Box 756, 2001 Industrial Drive Pocahontas, AR 72455 USA	Model: SHL21W PVC Single Hung Window Operator Type: H Config: All/EM Max Width: 46 Max Height: 60


Referenced Standard:	Product Rating:
AAMA 1701.2-95, AAMA 1704-85/12, 24 CFR 3280.305 (c)(1)(ii)(B)	Wind Zone III @58.0 PSF, 46x60, (Corner of wall / Field of wall)

Qualifying Test Information:	
Test Report No:	2812.02-109-12-R1
Test Report Expiration:	4/16/2025




Authorized Signature:

Aaron Shultz
07:51:36 2021.04.16  
'00'04-

Keystone Certifications, Inc.
145 Limekiln Rd. Suite 100B
New Cumberland, Pennsylvania 17070
Phone: 717-932-8500
Fax: 717-932-8501



**INSTALLATION METHOD
PVC (VINYL) SH21 SINGLE HUNG
ELEVATION & ANCHOR LAYOUT**



SCALE: NTS
DWN BY: AMM
CHK BY: KEA
DATE: 10/13/15

TITLE:
INSTALLATION METHOD
PVC (VINYL) SH21 SINGLE HUNG
ELEVATION & ANCHOR LAYOUT

PREPARED BY:
POCAHONTAS ALUMINUM COMPANY, INC.
2001 INDUSTRIAL DRIVE
POCAHONTAS, AR 72455
PH: 870-892-3689 FAX: 870-892-9858

REVISIONS			
NO.	DESCRIPTION	BY	DATE

COPYING OR
DUPLICATION IS
PROHIBITED WITHOUT
WRITTEN PERMISSION
FROM POCAHONTAS
ALUMINUM
COMPANY, INC.



TEST REPORT

AAMA 1701.2-95

AAMA 1704-85

AAMA 1704-12

REPORT NO.: 2812.02-109-12-R1

RENDERED TO: POCAHONTAS ALUMINUM COMPANY, INC.
Pocahontas, Arkansas

PRODUCT TYPE: PVC Single Hung Window 46-1/4 x 60-1/4

SERIES / MODEL: SHL21W

Test Date: 2/8/2021
Report Date: 2/22/2021
Revision Date: 2/22/2021

CLIENT INFORMATION: POCAHONTAS ALUMINUM COMPANY, INC.
2001 Industrial Drive
Pocahontas, Arkansas 72455

TEST LABORATORY: Molimo, LLC
1410 Eden Road
York, Pennsylvania 17402
717-900-6034

PROJECT SUMMARY:

PRODUCT TYPE: PVC Single Hung Window 46-1/4 x 60-1/4

SERIES/MODEL: SHL21W

PROJECT SUMMARY:

Molimo, LLC was contracted to perform testing on the above referenced product. The results are tested values and were secured by using the designated test methods. The specimen tested successfully met the performance requirements listed in the referenced specifications.

Specimen	Structural Load	Wind Zone Achieved
1	±2777 Pa (±58.0 psf)	Wind Zone III – Corner of wall Wind Zone III – Field of wall

PROJECT DETAILS:

Test Date: 2/8/2021

Test Record Retention End Date: 2/8/2025

Test Location: VEKA, Inc. test facility in Fombell, PA.

Test Specimen Source: The test specimen was provided by the client. Representative samples of the test specimen will be retained by Molimo for a minimum of four years from the test completion date.

Drawing Reference: The test specimen drawings were supplied by the client. The test specimen construction was verified by Molimo and was found to be representative of the product tested. A complete drawing packet is kept on file with Molimo.

WITNESSES:

The following representatives witnessed all or part of the testing.

Name	Company
Doug Merry	VEKA, Inc.
Cornell Charles	VEKA, Inc.
Joseph Allison	Molimo, LLC

TEST METHODS:

AAMA 1701.2-95 – *Voluntary Standard for Utilization in Manufactured Housing for Primary Windows and Sliding Glass Doors*

AAMA 1704-85 – *Voluntary Standard for Egress Window Systems for Utilization in Manufactured Housing*

AAMA 1704-12 – *Voluntary Standard for Egress Window Systems for Utilization in Manufactured Housing*

Code of Federal Regulations, Part 3280 – *Manufactured Home Construction and Safety Standards*, Subpart D, Section 3280.305(c)(1)(ii)(B)

TEST SPECIMEN DESCRIPTION:

Test Specimen #1				
Overall Area: 1.8 m ² (19.35 ft ²)	Width		Height	
	Millimeters	Inches	Millimeters	Inches
Overall Size:	1175	46-1/4	1530	60-1/4
Sash:	1124	44-1/4	768	30-1/4
Screen Size:	1137	44-3/4	746	29-3/8

TEST SPECIMEN DESCRIPTION: (Continued)
FRAME CONSTRUCTION:

Frame Member	Material	Detail
Head, Sill and Jambs	PVC	Extruded
Corner Construction	--	Miter-cut and thermally welded
Fixed meeting rail	PVC	Fastened to the jambs with four #8 x 3" pan head screws, two at each end. Each intersection was sealed with silicone sealant.

FRAME CONSTRUCTION:

Material: Extruded PVC

SASH CONSTRUCTION:

Sash Member	Material	Detail
Rails and stiles	PVC	Extruded
Corner Construction	--	Miter-cut and thermally welded

REINFORCEMENT:

Drawing Number	Material	Location
D-020921-D2	Extruded aluminum	Fixed meeting rail, lock rail, bottom rail, stiles

TEST SPECIMEN DESCRIPTION: (Continued)

GLAZING DETAILS: *No conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimen can be made.*

Description	Detail
Glass Type	5/8" IG
Glazing Construction (exterior to interior)	1/8" Thick annealed glass 3/8" Box shaped steel spacer, single sealed 1/8" Thick annealed glass
Glazing Method	Exterior glazed against a bed of silicone sealant and secured with rigid vinyl glazing beads.
Glazing Bite	1/2"
Daylight Opening Sash: Fixed:	1041 mm x 686 mm (41" x 27") 1111 mm x 686 mm (43-3/4" x 27")

WEATHERSTRIPPING:

Description	Quantity	Location
0.187" Backed by 0.270" high center fin pile	1 Row	Lock rail
0.187" Backed by 0.270" high center fin pile	2 Rows	Sash stiles, bottom rail

DRAINAGE:

Description	Quantity	Location
9/16" Wide by 5/32" high weep slot	2	Exterior sill face, one 2" in from each end.
9/16" Wide by 5/32" high weep slot	2	Interior sill track, one at each end
1/4" Diameter weep hole	2	Sill screen track, one at each end

TEST SPECIMEN DESCRIPTION: (Continued)
HARDWARE:

Description	Quantity	Location
Composite sweep lock	2	Lock rail, one 9" from each end mating with integral groove in the fixed meeting rail
Composite surface mount tilt latch	2	Lock rail, one at each end
Interlocking metal tilt pin	2	Bottom rail, one at each end
Block and tackle balance system	2	One per jamb

SCREEN CONSTRUCTION:

Frame Material	Formed aluminum
Corner Construction	Square cut and secured with snap-in plastic corner keys
Mesh Type	Fiberglass mesh
Mesh Attachment Method	Flexible vinyl spline

INSTALLATION: The specimen was installed into a Spruce-Pine-Fir wood buck. The rough opening allowed for a 1/8" shim space. The exterior perimeter of the specimen was sealed with sealant.

Location	Anchor Description	Anchor Spacing
Head, Sill, Jamb	#8 x 2" Truss head screw	Nominally spaced at 7-1/2" on center, and beginning at each corner fastened through the nailing fin and into the wood buck

TEST RESULTS: The temperature during testing was 19°C (67°F).

TEST SPECIMEN #1:

STRUCTURAL TESTING: (per ASTM E 330)

Test	Results	Allowable
+1190 Pa (+25.0 psf) -595 Pa (-12.5 psf)	Pass	No Damage

Note 1: All loads were held for 10 seconds.

Note 2: Tape and film were used to seal against air leakage. In our opinion, the tape and film did not influence the results of the test.

AIR LEAKAGE TESTING: (per ASTM E 283)

Test	Results	Allowable
Infiltration @ 75 Pa (1.57 psf)	1.9 L/s/m ² (0.38 cfm/ft ²)	2.5 L/s/m ² (0.50 cfm/ft ²)

WATER PENETRATION TESTING: (per ASTM E 331 and/or ASTM E 547)

Test	Results	Allowable
135 Pa (2.86 psf)	Pass	No Leakage

Note 3: Water Penetration testing was performed with and without an insect screen.

OPTIONAL STRUCTURAL PERFORMANCE TESTS: (per ASTM E 330)

Test	Results	Allowable
+2777 Pa (+58.0 psf) -2777 Pa (-58.0 psf)	Pass	No Damage

Note 1: All loads were held for 10 seconds.

Note 2: Tape and film were used to seal against air leakage. In our opinion, the tape and film did not influence the results of the test.

Note 3: Structural performance achieved meets Wind Zone II for the Positive and Negative directions for all areas including within 3'0" from each corner of the sidewall or endwall.

Note 4: Structural performance achieved meets Wind Zone III for the Positive and Negative direction for all areas other than within 3'0" from each corner of the sidewall or endwall.

SECONDARY TESTS:

Test	Results	Allowable
Safety Drop Test (per AAMA 1701.2)	Pass	Sash stops at the next lower position while retaining glass

TEST RESULTS: (Continued)

TEST SPECIMEN #1: (Continued)

AAMA 1704 TESTING


Test	Results	Allowable
Clear Opening Width	1137 mm (44-3/4")	510 mm (20") min.
Clear Opening Height	689 mm (27-1/8")	610 mm (24") min.
Clear Opening Area	0.8 m ² (8.4 ft ²)	0.5 m ² (5.0 ft ²) min.
Locks and Latches	53 N (12 lbf)	90 N (20 lbf) max.
Operable Sash	53 N (12 lbf)	90 N (20 lbf) max.
Removable Screen	44 kg (10lb)	9 kg (20 lb) max.

A copy of this report, detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation will be retained by Molimo, LLC for the entire test record retention period. At the end of this retention period, the service life of this report will expire.

Results obtained are tested values and were secured by using the designated test methods. This test report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen(s) tested. This report may not be reproduced, except in full, without the written permission of Molimo, LLC.

For MOLIMO, LLC:

Joseph E. Allison
Regional Project Manager



Michael D. Stremmel, P.E.
Senior Project Engineer

Attachments (pages): This report is complete only when all attachments listed are included.

Appendix-A: Drawings: (4)



2021.02.22 14:21:30 -05'00'

This report was produced from controlled document template MMO-00048, Rev 2, 8/28/2018.

Revision Log

Rev. #	Date	Page(s)	Revision(s)
1	2/22/2021	Cover, Page 1	Corrected state

Appendix A

Drawings



BILL OF MATERIALS

WELDED TILT SINGLE HUNG (SHL21WW Keeperless)

	Molimo Architectural Product Testing
Report #:	2812.02-109-12
Date:	2/17/2021
By:	J. Allison

NOTE: THIS BILL OF MATERIALS REFLECTS THE SYSTEM AS TESTED. DEVIATION FROM THE BILL OF MATERIALS IS NOT RECOMMENDED BY VEKA INC. AND MAY REDUCE THE PERFORMANCE OF THE FINISHED PRODUCT.

<u>PVC PROFILES:</u>	<u>PART #</u>	<u># PER UNIT</u>	<u>SOURCE</u>
JAMBS	SHL21	2	VEKA
HEAD	SHL21	1	VEKA
SILL	SHL23	1	VEKA
KEEPER RAIL	SHS214	1	VEKA
STILES / BOTTOM RAIL	SHS25	3	VEKA
LOCK RAIL	SHS26	1	VEKA
BALANCE COVER	BC01	2	VEKA
GLAZING BEADS	BVP01	8	VEKA
INTERMEDIATE JAMB	SHL220	A/R	VEKA

REINFORCING PROFILES:

NOTE: Refer to test reports in technical manual for reinforcing guidelines.

JAMBS (SHL21)		A/R	
SILL (SHL23)		A/R	
KEEPER RAIL (SHS214)	D-020921-D2	A/R	TOWER EXTRUSIONS
STILES / BOTTOM RAIL (SHS25)	D-020921-D2	A/R	TOWER EXTRUSIONS
LOCK RAIL (SHS26)	D-020921-D2	A/R	TOWER EXTRUSIONS

HARDWARE:

SWEEP LATCH	3174*	1-2	VISION
FLUSH MOUNT TILT LATCH ASSY	79910	1	ASHLAND
(STANDARD) OR	79915	1	ASHLAND
(WITH SCALLOP)	79920	1	ASHLAND
	79925	1	ASHLAND
BALANCE	INVERTED BLOCK AND TACKLE	2	AMESBURY
BALANCE SHOE		2	AMESBURY
PIVOT BAR		2	AMESBURY
DRYWALL CLIP	"L" BRACKET	2	HMS

GLAZING:

GLAZING SHIMS	5/8" X 5/8" X 1/8"	A/R	TREMCO
	5/8"x 5/8" x 1/8"	A/R	FRANK LOWE CO
GLAZING TAPE	1/16" X 1/2" (AWT)	A/R	ARLON
	1/16" X 1/2"	A/R	NORTON
	1/16" X 1/2"	A/R	VENTURE



BILL OF MATERIALS

WELDED TILT SINGLE HUNG (SHL21WW Keeperless)

NOTE: THIS BILL OF MATERIALS REFLECTS THE SYSTEM AS TESTED. DEVIATION FROM THE BILL OF MATERIALS IS NOT RECOMMENDED BY VEKA INC. AND MAY REDUCE THE PERFORMANCE OF THE FINISHED PRODUCT.

<u>GLAZING:</u>	<u>PART #</u>	<u># PER UNIT</u>	<u>SOURCE</u>
SILICONE SEALANT	NOVAFLEX**	A/R	NOVAGUARD
LIQUID BACK BEDDING	SBC1M150	A/R	NOVAGUARD
SILICONE	896	A/R	PECORA
	5733	A/R	SCHNEE MOREHEAD
	899	A/R	DOW CORNING

WEATHERSTRIPPING:

WEATHERPILE	.260-.187	FS7825-187 (WHITE)	A/R	SCHLEGEL
	.260-.187	3026W (WHITE)	A/R	ULTRAFAB
	.260-.187	26018758WHWF (WHITE)	A/R	AMESBURY

SCREWS:

NOTE: All screws are zinc plated or stainless steel sheet metal type, unless otherwise noted.

SWEEP LATCH		#6 X 3/4" FHP **	2-4	MERCHANTS
BALANCE		#8 X 1" FHP	2	MERCHANTS
PIVOT BAR		#6 X 3/8" TYPE F TRUSS HD	4	MERCHANTS
KEEPER RAIL		#6 X 1-1/2" THP	4	MERCHANTS
DRYWALL CLIP				
(CLIP TO JAMB)		#6 X 3/4" FHP	4	MERCHANTS
(CLIP TO KEEPER RAIL)		GRADE 10 #44	4	MERCHANTS
		BLIND RIVET		


** = COLOR
A/R = AS REQUIRED

	Molimo Architectural Product Testing
Report #:	2812.02-109-12
Date:	2/17/2021
By:	J. Allison

04/21/2016
REV.5/24/16

NC
FC
&
LI
SY

 **Molimo**
Architectural Product Testing
Report #: 2812.02-109-12
Date: 2/17/2021
By: J. Allison




The
thi
exc
cor
is
use
wri



DRAWN: BJF	DA'
CHK'D:	DA'
TITLE SINGLE HUNG SH VERTICAL ASSEMBLY	

NOTE:
 FOR OTHER PROFILE, GLAZING BEAD,
 & GLASS OPTIONS, PLEASE SEE THE
 LINEAL PROFILE CHARTS FOR THIS
 SYSTEM.



The information, design or data shown on this document or electronic media is the exclusive property of Veka Inc.. It is considered confidential and proprietary and is made available for limited use only. Its use or reproduction without the expressed written consent of Veka Inc. is prohibited.

Molimo
 Architectural Product Testing

Report #: 2812.02-109-12
 Date: 2/17/2021
 By: J. Allison



VEKA INC.
 100 VEKA DRIVE
 FOMBELL, PA 16123

DRAWN: B.J.F.	DATE: 15 FEB 21	SCALE: FULL
CHK'D:	DATE:	APPV'D:
TITLE: SINGLE HUNG SHL21WW HORIZONTAL ASSEMBLY		
DWG. # SHL21WW KL POCA STRUCT 2-15-21		